

DOD Experience from a Half Million Operating Hours of a PAFC Fleet

William R. Taylor
Dr. Michael J. Binder
Franklin H. Holcomb

*2000 Fuel Cell Seminar
Portland, Oregon
November 1, 2000*




US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

DoD FUEL CELL DEMONSTRATION PROGRAM

- FY93 Congressional Appropriation - \$18M
- FY94 Congressional Appropriation - \$18.75M
- Specify “...natural gas fuel cells in production in the United States...”




US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

Turn-key Package

- ONSI PC25 Fuel Cell Power Plant
 Fy93 - 1 ea. Model A, 11 ea. Model B
 Fy94 - 3 ea. Model B, 15 ea. Model C
- Engineering Design / Installation
- Training for Site Personnel
- 60 Months Maintenance
- Diagnostic / Remote Monitoring Computer





US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

PC25 POWER PLANT DoD SITES



US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

Facility Applications

- Central Heat Plants

11 Sites



- Hospital Utility Plants

7 Sites




- Pool / Gymnasiums

3 Sites



- Others

Barracks, Dining Facility, Laundry,
NG Armory, Launch Control Bldg.,
Office, Evaporator process



US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

FY93 Program Sites



934th Airlift Wing, Minneapolis MN



Kirtland AFB, Albuquerque NM



Nellis AFB, Las Vegas NV



Vandenberg AFB, Lompoc CA



US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

FY93 Program Sites




Naval Hospital, MCAGCC 29 Palms, 29 Palms CA



Naval Hospital, MCB Camp Pendleton, Oceanside CA



Naval Education Training Center, Newport RI



US Naval Academy, Annapolis MD



US Army Corps
of Engineers

Engineer Research & Development Center

FY93 Program Sites



U.S. Army Soldier Systems Command, Natick MA




Ft. Eustis, Newport News VA



Picatinny Arsenal, Dover NJ



U.S. Military Academy, West Point NY



US Army Corps
of Engineers

Engineer Research & Development Center

FY94 Program Sites



911th Airlift Wing, Pittsburgh PA




NAS Fallon, Fallon NV



Ft. Richardson, Anchorage AK



Naval Hospital, NAS Jacksonville, Jacksonville FL



US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

FY94 Program Sites



Edwards AFB, CA




Barksdale AFB, Bossier City LA



Ft. Huachuca, Sierra Vista AZ



National Defense Center for Environmental Excellence
(NDCEE), Johnstown PA



US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

FY94 Program Sites



CBC Port Hueneme, Port Hueneme CA




Laughlin AFB, Del Rio TX



Naval Oceanographic Office
John C. Stennis Space Center, MS



Westover ARB, Chicopee MA



US Army Corps
of Engineers

Engineer Research & Development Center

FY94 Program Sites



Ft. Bliss, El Paso TX




Subase New London, Groton CT



Little Rock AFB, Jacksonville AR



Pine Bluff Arsenal, White Hall AR



US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000


FY94 Program Sites



Watervliet Arsenal, Albany NY



Davis-Monthan AFB, Tucson AZ




US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

Fleet Performance

- Availability
- Outages
- Efficiency
- Cell Voltage
- Current Operating Status





US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

PC25B Availability

Lifelong Average for 14 Sites





US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

PC25B Availability

Monthly for Entire B Fleet





US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

PC25C Availability

Lifelong Average for 15 Sites





US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

PC25C Availability

Monthly for Entire C Fleet





US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

Mean Time Between Forced Outages

(as of Sep 2000)





US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

Average Duration of Outage

(as of Sep 2000)





US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

Causes of Forced Outages By Subsystem





US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

Causes of Forced Outages By Specific Cause



US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

Efficiency

At initial acceptance, power plants were required to demonstrate an output of 200 kW with a natural gas input of 1900 ± 100 cubic feet per hour.



Electrical Efficiency LHV = $39\% \pm \sim 2\%$

HHV = $35\% \pm \sim 2\%$

*based on 925 Btu/cf (LHV) and 1027 Btu/cf (HHV)

- avg from 10 sites





US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

Fleet B Lifelong Average Efficiency





US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

Fleet C Electrical Efficiency (LHV) Lifelong Average





US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

Average Cell Voltage for SN9059





US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

Average Cell Voltage B Fleet





US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

Average Cell Voltage C Fleet




US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000


B Fleet Events

- **5 Cell Stacks Replaced**
 - SN9061, Jan96 at 4K Op.Hrs
 - SN9068, May97 at 9K Op.Hrs
 - SN9060, Dec97 at 3K Op.Hrs
 - SN9062, Feb98 at 13K Op.Hrs
 - SN9070, Feb98 at 13K Op.Hrs
- **2 Units Shutdown for Removal**
- **1 Unit Shutdown by User**
- **1 Unit CSA Refurbishment (exp.)**




PC25B Current Status

As of Sep 2000



$$\text{AVG Operating KW} = \frac{45740 \text{ MWH}}{296245 \text{ RunHrs}} = 154 \text{ KW}$$




US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000

C Fleet Events

- **2 Cell Stacks Replaced**
 - SN9121, Oct97 at 2K Op.Hrs
 - SN9093, Aug99 at 15K Op. Hrs
- **3 CSA Replacements Planned**
- **SN9123 Rebuilt**




US Army Corps
of Engineers

Engineer Research & Development Center


30Jun2000

PC25C Current Status

As of June 2000



$$\text{AVG Operating KW} = \frac{56238 \text{ MWH}}{317051 \text{ RunHrs}} = 177 \text{ KW}$$



US Army Corps
of Engineers


Engineer Research & Development Center

30Jun2000

Fleet Performance Summary

(29 Power Plants)
As of 1 September 2000



- Total Run Time 614,658 hrs
- Availability
 - Model B Fleet 56%
 - Model C Fleet 77%
 - Last 6 months 83%
- Energy \$ Saved \$4,144,645
- NOx Abated 197 tons
- SOx Abated 422 tons
- CO Abated 17 tons
- CO₂ Abated 25,001 tons



US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000



US Army Corps
of Engineers

Engineer Research & Development Center

30Jun2000